Computer Systems for AI-inspired Cloud Theory & Lab.

SmartX Labs – Mini (MOOC Selection)


Tower (Lab#3)




















Lab Theory















SmartX Edge µBoxes



SmartX
Edge Cluster



SmartX
DevOps Tower
Cloud
with DataLake


End Edge Core

Things

μClouds SDN/NFV


Clouds (HPC/BigData)

- Software development technique based on Collection of loosely coupled small-size services (i.e., functions)
- Fine-grained services and lightweight protocols to improve modularity, create applications easier, and helps resiliency against architecture erosion






- Time series data is arrays of numbers indexed by time.
- In some fields these time series are called profiles, curves, or traces.



- Adopts a flexible notification mechanism
- User can configure & watch graph easily via Web GUI

- Consists of structured server and client
 - Client collects the monitoring data and send it to the Zabbix server
 - Server visualizes the data that is collected by the Zabbix Agent





Zabbix Server Agent structure

Ubuntu boot up phases

1. BIOS

2. Boot loader

The job of the boot loader is to begin the next phase, loading the kernel and an initial ram disk filesystem.


▶ The kernel launches the init script inside the initrd file system, which loads hardware drivers and finds the root partition.

3. Kernel

▶ After the kernel is running, the remainder of the operating system is brought online.


4. Upstart

Remote OS installation targets



Bare metal

- OS absent in the hardware
- For remote OS installation, the host doesn't have a decision-making power.



Mobile device

- OS already activated in the hardware
- From the standpoint of user, OS is installed automatically by host.



MAAS(Metal As A Service) is


better suited to the bare metal.



puppet











- Region Controller: Deals with operator requests
- Rack Controller: Provide the high bandwidth services to multiple server racks + Cache OS install images



- Bear-metal machines can be quickly provisioned and destroyed; MAAS provides management of a large number of physical machines by creating a single resource pool
- MAAS can act as a standalone PXE services, provides Web GUI, supports various Linux distribution installation, ...



Reference: https://docs.maas.io/2.4/en/intro-concepts#controllers



Warning!

Box Hardware Requirements for Automated Installation

- *IPMI, Intel AMT, IBM HMC, ...
- PXE bootable with DHCP option
- Two Ethernet interfaces

*IPMI: The intelligent Platform Management Interface. Remote hardware health monitoring and management system that defines the interfaces for use in monitoring

Remote OS installation Process

- 1. DHCP server contacted
- 2. Kernel, initrd received over TFTP
- 3. Machine boots
- 4. Initrd mounts a squashfs image over HTTP







Enlistment

- 5. cloud-init runs enlistment scripts
- 6. Machine shuts down



Commissioning

- 5. cloud-init runs commissioning scripts
- 6. Machine shuts down



Deployment

- 5. cloud-init triggers deployment
- Curtin installation script run
- Squashfs image placed on disk





Lab Practice

Wired connection

NAME: Raspberry Pi Model B (Pi)

CPU: ARM Cortex A7 @900MHz

CORE: 4

Memory: 1GB

SD Card: 32GB

NAME: NUC5i5MYHE (NUC PC)

CPU: i5-5300U @2.30GHz

CORE: 4

Memory: 16GB DDR3

HDD: 94GB

NAME: NT900X3A

CPU: i5-2537U @1.40GHz

CORE: 2


Memory: 4GB DDR3

HDD: 128GB




NAME: netgear prosafe 16 port gigabit switch(Switch) **Network Ports:** 16 auto-sensing 10/100/1000 Mbps

Ethernet ports




Are they working?

If you can see logs of resource status on console consumer, go ahead!



- Run InfluxDB Container
 - \$ docker run -d --name=influxdb --net=host influxdb



\$ docker run -p 8888:8888 --net=host chronograf --influxdb-url=http://<NUC IP>:8086



- Install python-pip
 - \$ sudo apt-get install -y libcurl3 openssl curl
 - \$ sudo apt-get install -y python2.7 python-pip
 - \$ sudo apt-get install -y python3-pip



- \$ sudo pip install requests
- \$ sudo pip install kafka-python
- \$ sudo pip install influxdb
- \$ sudo pip install msgpack




Open 'broker_to_influxdb.py' code


\$ vi ~/SmartX-mini/ubuntu-kafkatodb/broker_to_influxdb.py


- Run python code
 - \$ sudo sysctl -w fs.file-max=100000
 - \$ ulimit -S -n 2048
 - \$ python ~/SmartX-mini/ubuntu-kafkatodb/broker_to_influxdb.py


.........

 Open Web browser and connect to Chronograf Dashboard http://<NUC IP>:8888













<u>.....</u>


• We can see the changes of values from database











Requirements for manual Installation

- DHCP PXE bootable
- USB to ethernet connector

Note: Typical NUC does not have a IPMI port.

- From target NUC, go to BIOS, turn on PXE and set network boot priority
- NUC reboot (to apply BIOS changes)
- Install MAAS server
 - \$ sudo apt update
 - \$ sudo apt install maas
- Initiate MAAS server
 - \$ sudo maas init
- Login to the MAAS UI at: http://<your.maas.ip>:5240/MAAS
- From the MAAS UI, you need to make user configurations
- *Region name
- Ubuntu images
- Turn on DHCP
- Go to the "Subnets" tab, select the VLAN for which you want to enable DHCP
- From the "Take action" button select "Provide DHCP"



- Fnlist the NUC
- Set all the servers to PXE boot
- NUC reboot (When hardware is initialized, all software operations stop)
- Check the NUC appear in MAAS
- If the NUC does not support IPMI based BMC, edit them and enter their BMC details
- Commission the NUC
- Go to "machine interface", "configuration" and set "power type" to "manual"
- From the "take action" button, select "commission"
- NUC reboot (When a new kernel is installed, the box must be rebooted as to prevent the removed kernel from being loaded which will halt the NUC operation)
- Deploy the NUC
- From the "take action" button, choose "deploy" and click "view this page"
- From SSH keys, choose source and click upload
- Set "id_rsa.pub" as a public key and click "import"

- Create SSH key
 - \$ sudo ssh-keygen
 - \$ sudo cat ~/.ssh/id_rsa.pub


Copy the outcome, press "upload" and paste it on "User ID" and import


- Deploy
- From "take action", choose "deploy"
- OS remote Install complete

Appendix

Remaining Lab practice requires special Box resources with IPMI or similar Remote Power Management, PXE Boot support









Requirements for Automated Installation

- IPMI, Intel AMT, IBM HMC ... and so on.
- DHCP PXE bootable

Note: Typical NUC does not satisfy the above requirement!







<BIOS PXE Configuration>


<BIOS IPMI Configuration>

- After then Save Configuration and Exit
- And then the PXE booting sequence is stated






It takes about 10 minutes



- It is a OS Installation procedure
- It takes about 15 minutes





Lab Review

With Tower Lab, you have experimented selected roles of Monitor/Control (관제) Tower

01

Visibility Center function to **enable 'distributed monitoring'** over remote Boxes and to **store** 'monitoring information' to time-size DB.

02

Provisioning Center function to **enable remote** 'installation & configuration (of OS and others)' of distributed Boxes.

Thank You for Your Attention Any Question?

Mini@smartx.kr

